

## **Mhlontlo Local Municipality**

Project Name: Construction of Nodali to Madiba Access Road

Bid Number: (MIG/R/EC/1900/22/24)

Date: 24 July 2023

NOTICE TO TENDERERS NUMBE	ER 1:	ADDENDA	NO:	: 1
---------------------------	-------	---------	-----	-----

THIS NOTICE MUST BE COMPLETED BY TENDERERS AND RETURNED WITH THE TENDER DOCUMENT, SIGNED AND BOUND UNDER RECORD OF ADDENDA PAGE 140

1.1 Replacement of tender page 140 under BO
---

- Replace BOQ singular page on tender document page 140 with the one attached.								
Kindly ensure that page 84 is signed to	acknowledge reco	ord of addenda to tender documents						
PRINT NAME	1	SIGNATURE						

WORKS PART 3 (OF 4): SCOPE OF MHLONTLO LOCAL MUNICIPALITY: CONSTRUCTION OF NODALI TO MADIBA ACCESS ROAD (MIG/R/EC/1900/22/24)

MHLONT LO LOCAL MUNICIPALITY
BID NO: MIG/R/EC/1900/22/24
CONSTRUCTION OF NODALI TO MADIBA ACCESS ROAD (16KM)
BILL OF QUANTITIES (Re-me asurement Contract)
SEPTEMBER 2022

ITEM NO	PAYMENT REFERS	LIC	SHORT DE SCRIPTION	UNIT	QTY	RATE	AMOUNT
	SA BS 1200 DM		SECTION DM: EARTHWORKS (ROADS) SUBGRADE				
DM1 DM1.1	PSOM83.3		TREATMENT OF ROADBED Rip roadbed to a depth of 150mm remove oversize material and compact to				
OM5	8.3.7		93% Mod AASHTO density Cut to spoil:	m,	14,400		
DM5.1			(a) From soft material and transport spoil material to unspecified sites and dump	un,	720		
OM5.2			(b) From intermediate material and transport spoil material to unspecified sites and dump	uı,	432		
DM5.3			(c) From hard material and transport spell material to unspecified sites and dump	ms	144		
	MOS		Cut to fill Compact to 90 % mod. AASHTO maximum density	m³	2.500		
			Rockfill, process, and compact	un,	100		
	8.3.4		Borrow to fill				
			Compact to 90 % mod. AASHTO maximum density	m <sup>s</sup>	750		
	8.3.6		Extra-over items 12.7 to 12.9 inclusive for excavating and breaking down material in:				
		ı	Intermediate excavation	LLI,	50		
		ı	Hard excavation Boulder excavation Class A	ms ms	10		
			Boulder excavation Class B	uı,	10		
	8.3.11		Extra-over items 12.7 and 12.8 for temporary stockpiling of material	uı,	13,800		
	8.3.12		Borrow pits (see Section D)  OVERHAUL  Extra-over items for hauling material in	m³	3,000		
			excess of the freehaul of 0,5km but not more than 1,0km	(anda)			
			Extra-over item 12, 18, 1 for hauling material in excess of the haul of 1,0 km	mª.km	12,000		
	8.3.16		GRAVEL SURFACING Gravel surface layer with material form borrow pit	m²	13,800		